

SPC herringbone flooring is designed to be installed as a "floating" floor. Do not secure the planks to the subfloor. Always undercut wood doorjambs. Check local building code for metal door jamb. If they cannot be cut, then proper expansion must be maintained around door jamb.




1. Getting started. Choose a wall to start at and begin installing at the left corner. Start with an A-panel and place it with its long side $marking \, facing \, the \, left \, wall \, at$ an angle of 45°. Make sure that the distance between the left wall and the panel is less than the length of one panel.




2. Connect next panel Continue with a B-panel. Press the long side of the B-Panel at an angle against the short side of the previous installed Apanel. Fold down the B-panel flat to the floor to lock the panels tightly together. Check that the grooves on the two panels form a continuous line.




3. Connect additional panels Next panel is an A-panel. Again, press the long side of the new A-panel at an angle against the short side of the previous B-panel and fold down. Continue like this with as many panels as may fit along the starting wall.




4. Center the first row Check that the first row of panels is centered along the starting wall. Make sure that the distance to the walls on both sides are less than the length of one panel. If not,




5. Cut the end panels to size Measure and cut the end panels to size using a fine toothed saw. Finish the first row with the cut end panels. Make sure that you leave a gap of 10mm to each wall.



6. Start the second row Start the next row with an A-panel. Place the new panel against the previous row and fold down.




Continue from the left to the right and install all the A-panels in the second row. Finish with a piece of panel cut tosize (step 5).




-F


8. Continue with the B-panels Now work in the opposite direction, from the right to the left and install all the B-panels in the second row. Finish with a piece of panel cut to size (step5)





9. Complete four rows Install additional rows to complete four full rows.




10. Adjust the starting rows The first four rows have to be cut parallel to the wall. Measure and mark where to cut the floor panels at a fixed / parallel distance to the wall.









11. Dismantle and cut Number the panels from ${\bf 1}$ to \ldots . This will allow you to keep the panels in order. Dismantle the panels and cut them to size along the previous marked line.







Leave the left end-panels uninstalled. Tape along the marked line and place the flooring on top of a few flooring packages. Cut along the marked line. Then put the adjusted rows into place. Complete the first rows by installing the remaining end-panels. Start with the end-panel in the last row and finish at the first row




triangular shapes, one by one. Start installing the triangles from the left corner. It is recommended to use glue to fix the smallest parts of the triangles into place by applying a small quantity of glue inside the groove.




each row from the left to the right with the A-panels, finish with the cut piece of panel (step 5) and then install all the B-panels in the row. Finish with the left end panel, cut to size.









or beadings.





glue inside the groove.

panels. Apply a small quantity of



17. Spacers and skirting Remove the spacers and cover the expansion gap with skirting boards

SPC Herringbone Flooring is supplied by

TILE MERCHANT